

**Annexure-2**

System Improvement, DTC metering and 33/11kv Station Works carried out during 2016-17, 2017-18, 2018-19 for reduction of technical losses in the distribution network

Sl.No.	Particulars	16-17	17-18	18-19
1	DTC Added (Nos.)	1225	1391	1380
2	HT Reconductoring (RKMs)	171.00	160.02	193.40
3	HT line including 11KV Express Link Lines in (RKMs)	542.49	555.29	786.60
4	LT line reconductoring in (RKMs)	537.44	602.07	703.10
5	LT lines in (RKMs)	82.26	135.09	126.78
6	a) New 33 KV Stations (Nos/MVA)	1/5	1/10	2/15
	b) New 33 KV Lines	7	17.65	57.25
	c) Augmentation of 33 KV Stations (Nos/MVA)	4/27.5	4/42.5	2/10
7	Distribution Loss (in %)	11.4	11.32	10.52
8	Units saved under E&I works (MU)	26.08	17.99	41.46
9	Units saved under Station works(MU)	2.69	5.07	3.04
10	CAPEX incurred for E&I works (Rs. In Lakhs)	6520.62	9029.03	10980.34
11	CAPEX incurred for Station works (Rs. In Lakhs)	1814.6	2274.22	2005.14
12	CAPEX incurred for DTC Metering (Rs. In Lakhs)	1941.93	5260.77	1843.81
13	Total Number of DTCs Metered as at the end of year	37083	39418	43673
14	% of DTC Metering	62.67	58.97	58.17
15	Number of DTCs Audited	5950	9107	11716

*duich*  
24/12